

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Loewen Operator, Inc.
 Address: PO Box 335, Canton, KS 67428
 Phone: (620) 628-4425 Operator License #: 5631
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Steve Durrant (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-20, 284 -00-00
 Lease Name: Estes
 Well Number: 3
 Spot Location (QQQQ): _____ - SE - SE - NE
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 5 Twp. 22 S. R. 14 East West
 County: Stafford
 Date Well Completed: 8-23-1970
 Plugging Commenced: 10-31-06
 Plugging Completed: 11-1-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	450	
				5 1/2	3851	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded off bottom, loaded hole with water, dug out casing head, changed over to run tubing, checked hole, sand at 3780', bailed 5 sacks cement with bailer, ran 30 joints tubing down to 930', circulated with 80 sacks to surface, pulled tubing out, filled casing with 30 sacks, stayed full, tied on to 8 5/8", mixed 5 sacks, had 600 psi, tore down floor and rig, cut surface off 4' below ground, cleaned up location


Name of Plugging Contractor: Quality Well Service License #: 31925
 Address: 401 W Main, Lyons, KS 67554

RECEIVED
DEC 05 2006
KCC WICHITA

Name of Party Responsible for Plugging Fees: Loewen Operator, Inc.
 State of Kansas County, McPherson, ss.
Douglas D. Loewen, President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Douglas D. Loewen, Pres
 (Address) P.O. Box 335, Canton, KS. 67428

SUBSCRIBED and SWORN TO before me this 27th day of November, 20 06
Thomas L. Kueser My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PGT