

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-00407-00-00  
Spot: SENW Sec/Twnshp/Rge: 12-2S-28W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: ANNA Well #: 1  
County: DECATUR Total Vertical Depth: 3480 feet

Operator License No.: 31100  
Op Name: ROBUCK, BRETT DBA ROBUCK PETRO  
Address: PO BOX 345  
MCCOOK, NE 69001

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3468	0	75 SX
SURF	8.625	147	0	100 SX

**\$ 113.10**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2006 11:00 AM  
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY  
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK, DON E. DBA ENERGY SE Phone: (308) 340-3242

Proposed Plugging Method: Ordered 225 sxs Swift Multi-Density Cement and 600# hulls.  
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2006 6:45 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 147' w/100 sxs.  
5 1/2" production casing at 3468' w/75 sxs.  
PBTB 3468'. Production casing squeezed from 1793' - 1823' w/300 sxs.  
Ran tubing to 2500' - pumped 60 sxs with 400# hulls.  
Pulled tubing to 1200' - pumped 70 sxs cement with zero hulls - cement to surface.  
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 70 sxs cement.  
Max P.S.I. 650#. S.I.P. 250#.  
Connected to 8 5/8" surface casing - pumped 25 sxs cement.  
Max P.S.I. 275#. S.I.P. 250#.

**Perfs:**

Top	Bot	Thru	Comments
3468	3475	OH	

**INVOICED**

DATE 12-7-06  
INV. NO. 2007060932

Remarks: SWIFT SERVICES, INC.-TICKET #11145.

Plugged through: TBG

District: 04

*MD*

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 05 2006

KCC WICHITA

NOV 28 2006

*PPT*

JOHN O FARMER

#1 ANNA

12-2-28W  
C SE NW

Contr. JOHN O FARMER

DECATUR County

E 2503DF Comm. 5/30


Comp. 8/9/62

IP 90 BOPD, NW/LANS  
3468-80

Tops	Depth	Datum
ANH	2080	+423
HEEB	3344	-841
LANS	3389	-886
TD	3480	-977

**Casing**  
 8" 147/100  
 5" 3468  
 DST 3440-80/30", 390' G, 750' CL  
 GSY 0, FBHP 1141#/30", FP 62-  
 290#  
 CO TD: FU 200' 0/30": FU 2700'  
 OIH

OLIVE



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS