

6070288

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-168-22, 588-00-00

TECHNICIAN'S PLUGGING REPORT

SW-SE-NW, SEC. 14, T. 9 S, R. 17 W

2970 feet from S section line

3630 feet from E section line

Operator License # 8925

Lease Name MESTHUSING Well # 1 "C"

Operator: LIBERTY OPERATIONS

County ROOMS 115.05

Address AND COMPLETIONS, INC

Well Total Depth 3540 feet

308 WEST MILC

Conductor Pipe: Size 0 feet

PLAINVILLE, KANS. 67663

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 256

Plugging Contractor PIONEER DRILLING INC License Number 5665

Address 308 WEST MILC PLAINVILLE, KANS. 67663

Company to plug at: Hour: 9:00 AM Day: 12th Month: JAN Year: 1985

Plugging proposal received from TOM FLINN

(company name) PIONEER DRILLING INC (phone) 913-434-4686

were: 8 5/8" 218' 50" DRILL MUD 1/40 140 PERMIX GEL - 3% CA-CL (BY FLUID)

ORDER 220 1/50 PERMIX GEL - CA-CL - 1" FLAKE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - RECONDITION HOLE (50' H²O) HEAVY MUD BETWEEN ALL PLUGS.

ARBUCKLE @ 3512 - ELV 2064 - ANH. 1313, MUD, VIS. 46 - Weight 9.8

CHLORIDES 23 - NO CIRCULATION PROBLEMS.

Plugging Proposal Received by Mason Schmidt
BOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 AM Day: 12th Month: JAN Year: 1985

ACTUAL PLUGGING REPORT ORDERED 220 1/50 PERMIX GEL - CA-CL - 1" FLAKE & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM, RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 3480 FT M/25 SK CNT 2nd PLUG @ 1330 FT M/25 SK CNT

3rd PLUG @ 820 FT M/100 SK CNT 4th PLUG @ 270 M/50 SK CNT

5th PLUG SOLID BRIDGE PLUG @ 40 FT TO 0 M/10 SK CNT.

10th RAT HOLE (CIRCULATE) CEMENTED BY FLUID

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1985

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed Mason Schmidt
BOIC (TECHNICIAN) 1-16-85
mmg