

11-2 15-163-03347-00-00

8-26-49

6 040968

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW NW NW, SEC. 15, T 9 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Operator: Harold Kruger Co.

Name & Address: Natoma, Ks. 67651

_____ feet from S section line

_____ feet from E section line

Lease Name Carmichael Well # 2

County Rooks 114.34

Well Total Depth 3518 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 185' cwc

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks.

Company to plug at: Hour: 10:00AM Day: 2 Month: Nov Year: 19 88

Plugging proposal received from Dean Wineland

(company name) Kruger 001 (phone) _____

were: 5 1/2" casing set at 3518' w/ Top perf at 3217'.

Perf anhy at 1375' and base Dakota at 700'. Perf at 175'. Tubing fish at 2800'.

Ordered 300 sks 65/35 Poz 10% Gel w/ 1/2# P.C. plus 3 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:30PM Day: 2 Month: NOV Year: 19 88

ACTUAL PLUGGING REPORT Plugging report: Ran tubing to 2780'; pumped 90 sks

cement; pulled tubing to 1275'; ^{below} perf tubing at 1375'; pumped 60 sks cement; pulled

tubing to 685'; perf casing at 700'; pumped 50 sks cement; pulled tubing; perf casing

base S.P. at 175'; circ cmt to surf; pumped in 100 add sks cement. Job completed.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED I will please serve this plugging.

DATE 1-5-89

INV. NO. 23492

Signed Dennis L. Hamel (TECHNICIAN) Dennis Hamel

RECEIVED STATE CORPORATION COMMISSION 12/29/88 DEC 30 1988

CONSERVATION DIVISION Wichita, Kansas