

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-19024-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 12-2S-28W
506 feet from S Section Line, 4715 feet from E Section Line
Lease Name: OLIVE UNIT Well #: 3
County: DECATUR Total Vertical Depth: 3627 feet

Operator License No.: 31100
Op Name: ROBUCK, BRETT DBA ROBUCK PETRO
Address: PO BOX 345
MCCOOK, NE 69001

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3620	0	100 SX
SURF	8.625	178	0	125 SX

\$ 117.88

Well Type: EOR UIC Docket No: E17441.1 Date/Time to Plug: 11/17/2006 9:00 AM
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK, DON E. DBA ENERGY SE Phone: (308) 340-3242

Proposed Plugging Method: Ordered 215 sxs Swift Multi-Density Cement and 600# hulls. Plug thru tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2006 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 178' w/125 sxs.
5 1/2" production casing set at 3620' w/100 sxs.
PBTD 3620'. Production casing squeezed from 1605' - 2595' w/300 sxs.
Ran tubing to 2655' - pumped 60 sxs with 500# hulls.
Pulled tubing to 1320' - pumped 65 sxs cement with zero hulls - cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max P.S.I. 400#. S.I.P. 400#.
Connected to 8 5/8" surface casing - pumped 20 sxs cement.
Max P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3480	3484		

INVOICED
DATE 12-7-06
INV. NO. 2007060932

Remarks: SWIFT SERVICES, INC.-TICKET #11144.

Plugged through: TBG

District: 04

PD

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED Form CP-2/3

DEC 05 2006

KCC WICHITA

NOV 28 2006

PLG

12-2-28W

MURFIN DRILLING & RAINS-WILLIAMSON #3 MILLER 10' APP C SW SW
 (130' SOUTH)

Contr. RAINS & WILLIAMSON DECATUR County

22493 Comm. 7-4 Comp. 8-2-62 IP 90 BOPD NW, LANS
3480-84, GR 38°

SMP	Tops	Depth	Datum
TOP		3197	- 704
HEEB		3357	- 864
TOR		3393	- 900
L/KC		3402	- 909
TD		3627	-1134


Casing
 12" 178/125
 5" 3620

DST 3366-3415 /1HR, 30' SL O SPEC M, BHP
 1205-817//30", FP 28-36:

DST 3450-95/2 HRS, 135' V H OCM, BHP 1117-
 762//30", FP 39-86/:

CO: PERF 16/3480-84: SWB 8 GALS OIL PH, NW/
 3 HRS, 2000 ACID, SWB LD, FU 2100' OIL:
 SWB DN, SWB 26 BO, NW /1HR:

OLIVE POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS