

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23245-00-00  
Spot: S2NE Sec/Twnshp/Rge: 36-10S-23W  
2010 feet from N Section Line, 1340 feet from E Section Line  
Lease Name: MCCALL Well #: 2-36  
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 3293

Op Name: RUSSELL OIL, INC.

Address: P.O. BOX 1469  
PLAINFIELD, IL 60544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

\$ 122.69

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/24/2006 3:00 PM

Plug Co. License No.: 5184

Plug Co. Name: SHIELDS OIL PRODUCERS INC

Proposal Rcvd. from: BURT BEERY

Company: SHIELDS OIL PRODUCERS INC

Phone: (785) 483-3141

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

Witness Type: NONE

Date/Time Plugging Completed: 11/24/2006 4:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

No ar buckle found.  
1st. Plug at 1775' w/25 sxs.  
2nd. Plug at 1000' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

INVOICED  
DATE 12.7.06  
INV. NO. 2007060934

Remarks: QUALITY WELL SERVICE.

Plugged through: DP

District: 04

Signed *Case Morris*

(TECHNICIAN)

RECEIVED

DEC 07 2006

KCC WICHITA

NOV 28 2006