

KCC PERFORM PERFORMS Pigs
12/6/06

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22229-00-01

Spot: ~~NE~~ NEWSONE Sec/Twnshp/Rge: 18-9S-24W

~~3931~~ 1320 feet from ~~N~~ Section Line, 1330 feet from E Section Line

Lease Name: HENRY 1983 Well #: 1

County: GRAHAM

Total Vertical Depth: 4100 feet

Operator License No.: 6677

Op Name: SANDLIN OIL CORPORATION

Address: 621 - 17TH ST., STE 2055
DENVER, CO 80293

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4100	1004	w/125 sxs cement \$ 133.25
SURF	8.625	252	0	w/unknown sxs cement

Well Type: DL DH PST UIC Docket No: _____ Date/Time to Plug: 11/21/2006 8:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: TERRY GARRISON Company: SANDLIN OIL CORPORATION Phone: (303) 292-3313

Proposed 11/21/2006 - Ordered out 350 sxs 60/40 pozmix - 10% gel with 1/4# flocele per sack and 400# hulls.
 Plugging 11/22/2006 - Ordered out 55 sxs 60/40 pozmix - 10% gel.
 Method: Fluid level 1600'. Est. TOC 3500'. Port collar 2318'. Anhy. 2184' - 2280'.

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/22/2006 10:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Took injection rate 2 bpm 700#.
 Allied pumped 50 sxs 60/40 pozmix - 10% gel w/50# hulls.
 Displaced to 2700' at 1500#.
 Bleed off and ran free point tool.
 Pipe stuck at 1500'. Ran cut off tool to 2326'. Port collar at 2318'.
 Allied mixed 10 sxs gel - broke circulation - worked pipe.
 Pumped 110 BBL - pipe still stuck.
 Allied pumped 125 sxs cement with 200# hulls.
 Displaced to 1500' - shot pipe off again at 1004'.
 Allied pumped 175 sxs cement - did not circulate.
 Pulled casing out of hole - will run tubing and tag cement tomorrow.
 11/22/2006 - Ran tubing to 360' - tagged cement.
 Allied pumped 55 sxs and circulated cement.
 PTOH. Topped with cellar cement.

Perfs:

Top	Bot	Thru	Comments
4058	4060		
4036	4038		
4020	4025		
3840	3842		

INVOICED

DATE 12-7-06
INV. NO. 2007060935

Remarks: ORIGINALLY KNOWN AS KEITH HENRY #1-BLACK PETROLEUM COMPANY.

Plugged through: CSG

District: 04

Handwritten initials

Signed Richard Williams

(TECHNICIAN)

RECEIVED *PST*

DEC 01 2006

KCC WICHITA

NOV 28 2006