

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25584-00-00

Spot: NESE

Sec/Twnshp/Rge: 8-13S-16W

2110 feet from S Section Line,

800 feet from E Section Line

Lease Name: DINKEL

Well #: 1

County: ELLIS

Total Vertical Depth: 3500 feet

Operator License No.: 9292

Op Name: SCHECK, TIMOTHY DBA SCHECK OIL

Address: 225 MAIN
RUSSELL, KS 67665

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
<u>SURF</u>	<u>8.625</u>	<u>221</u>		

\$ 113.75

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/06/2006 5:00 AM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: SCHECK OIL OPERATION

Phone: (785) 483-3404

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 11/06/2006 7:00 AM

KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

No arbuckle found.
1st. Plug at 1150' w/25 sxs.
2nd. Plug at 675' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 12-7-06
INV. NO. 2007060936

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

(TECHNICIAN)

RECEIVED

DEC 05 2006

KCC WICHITA

NOV 30 2006