

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00434-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 7-24S-33W
2488 feet from S Section Line, 2490 feet from E Section Line
Lease Name: SHRIMPLIN GAS UNIT Well #: 1
County: FINNEY Total Vertical Depth: 2650 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2639		900 SX
SURF	8.625	847		500 SX

\$ 86.13

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2006 8:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: DEANN SMYERS Company: _____ Phone: (281) 366-4395

Proposed Plugging Method: 800# HULLS 7 75 SX CMT 60/40 POZMIX 4% GEL . FILLED 5 1/2 CSG WITH AN ADDITIONAL 148 SX 60/40 POZMIX 4% GEL. PRESSURE TO 300#. TOTAL CMT DOWN 5 1/2 = 223 SX 60/40 POZMIX 4% GEL HOLDING 5". HOOK UP TO 5 1/2 x 85/8 ANNULUS. PUMP 11 SX 60/40 POZMIX 4% GEL & PRESSURE TO 250#. (HAD OLD BOLTED BRODEN HEAD ON WELL)

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2006 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

800# HULLS 7 75 SX CMT 60/40 POZMIX 4% GEL . FILLED 5 1/2 CSG WITH AN ADDITIONAL 148 SX 60/40 POZMIX 4% GEL. PRESSURE TO 300#. TOTAL CMT DOWN 5 1/2 = 223 SX 60/40 POZMIX 4% GEL HOLDING 5". HOOK UP TO 5 1/2 x 85/8 ANNULUS. PUMP 11 SX 60/40 POZMIX 4% GEL & PRESSURE TO 250#. (HAD OLD BOLTED BRODEN HEAD ON WELL)

Perfs:

Top	Bot	Thru	Comments
2639	2650		OPEN HOLE
2512	2620		

INVOICED


DATE 12-11-06
INV. NO. 2007060943

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON

Plugged through: CSG

District: 01


Signed



(TECHNICIAN)

RECEIVED
DEC 06 2006
KCC WICHITA

Form C-27



PPT