

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-00009-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 36-22S-41W
2011 feet from S Section Line, 2176 feet from E Section Line
Lease Name: BRADSHAW Well #: 1
County: HAMILTON Total Vertical Depth: 5417 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8.625	2625		400 sx cmt
SURF	13.38	274		250 sx cmt

\$176.05

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2006 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOE BROUGHER Company: _____ Phone: (620) 277-0803

Proposed Plugging Method: PLUG SET CIBP AT 2500' AND 4 SX CMT. PLUG SET CIBP AT 1160' AND 4 SX CMT. PLUG TESTED CASING TO 500 #. EST. INJECTION RATE OF 1.25 BPM AT 675 #. MIXED AND PUMPED 300 SX 60/40 POZMIX 6% GEL. S.I. AT 75 #. PLUG PUMP 170 SX DOWN 8 5/8 X 13 3/8 ANNULUS. SHUT PSI 200 #.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2006 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP AT 2500' AND 4 SX CMT. 2ND PLUG SET CIBP AT 1160' AND 4 SX CMT. 3RD PLUG TESTED CASING TO 500 #. EST. INJECTION RATE OF 1.25 BPM AT 675 #. MIXED AND PUMPED 300 SX 60/40 POZMIX 6% GEL. S.I. AT 75 #. 4TH PLUG PUMP 170 SX DOWN 8 5/8 X 13 3/8 ANNULUS. SHUT PSI 200 #.

Perfs:

Top	Bot	Thru	Comments
2548	2610		

INVOICED
DATE 12-11-06
INV. NO. 2007060994

Remarks: USED 60/40 POZMIX 6% BY ALLIED

Plugged through: CSG

District: 01

Signed Steve Dunnet for KJ
(TECHNICIAN)

RECEIVED Form CP-2/3
DEC 06 2006
KCC WICHITA