

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20992-00-00
Spot: NESE Sec/Twnshp/Rge: 15-21S-21W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: HULING AB Well #: 7
County: HODGEMAN Total Vertical Depth: 4370 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, STE 2000
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3510		2 SX
CIBP		4215		1.5 SX
PROD	5.5	3493	2431	235 SX
SURF	8.625	1285		730 SX

\$ 142.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MR. DAVE STAHL Company: _____ Phone: (785) 625-4052

Proposed Plugging Method: SAND AND 5 SX CMT TO 3300'. 1ST PLUG AT 1310' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT TO SURFACE

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2006 2:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND AND 5 SX CMT TO 3300'. 1ST PLUG AT 1310' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT TO SURFACE

Perfs:

Top	Bot	Thru	Comments
4299	4305		MISSISSIPPIAN
3742	3957		LANSING KANSAS
3360	3456		TOPEKA

INVOICED

DATE 12-11-06
INV. NO. 2007060944

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT, INC. RECOVERED 2431' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
DEC 06 2006
KCC WICHITA

Form CP-2/3

[Handwritten Signature]