

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21371-00-00
Spot: SE Sec/Twnshp/Rge: 15-21S-21W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HULING AB Well #: 9
County: HODGEMAN Total Vertical Depth: 4830 feet

Operator License No.: 32754
Op Name: ELYSIUM ENERGY, L.L.C.
Address: 1625 BROADWAY, STE 2000
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4630	2427	250 SX
SURF	8.625	1259		650 SX

\$ 156.98

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/28/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MR. DAVE STAHL Company: _____ Phone: (785) 625-4052

Proposed Plugging Method: SANDED TO 4230' AND 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1290' WITH 15 SXGEL - 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2006 12:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4230' AND 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1290' WITH 15 SXGEL - 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4314	4324		
4308	4318		
4288	4298		

INVOICED
DATE 12-11-06
INV. NO. 2007060946

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
DEC 06 2006
KCC WICHITA

Form CP2573

[Handwritten signature]