

15-163-00931-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9/11/59
SEP 1 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks

Location: SE SE NE Sec. 15 Twp. 9 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3503

I have this date completed supervision of plugging of:

Lease Name: Westhusin Well No. 1

Operator's Full Name: Herndon Drg Co

Complete Address: Box 436 Lyons, Kans

Plugging Contractor: same & Globe Cementing Co

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7:30 PM Day 25 Month 8 Year 59

The above well was plugged as follows:

8 5/8" 203' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 540', displaced

20 sax cement through drill pipe, mud to 180', set cementing plug

and displaced 20 sax cement through drill pipe, heavy mud to 40'

set cementing plug, 1/2 sack hulls and 10 sax cement to 0'

Cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 4/6/60
INV. NO. 227W