

To: **6 070652**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-23-88 15-163-2B35-00-01
API NUMBER 15-20, 286-00-01
NE NE SE, SEC. 31, T 9 S, R 17 **(W)E**

_____ feet from S section line
_____ feet from E section line
Lease Name Ganoung Well # SWD OWWO
County _____ Rooks 43.39
Well Total Depth 1335 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 157

TECHNICIAN'S PLUGGING REPORT
Operator License # 5900
Operator: LABANCO
Name & Address Labanco Drilling Co.
Box 289
Natoma, Ks. 67651

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co. License Number _____

Address East Hwy 40 Hays, Ks. 67601

Company to plug at: Hour: 9:00AM, Day: 23 Month: March Year: 19 88

Plugging proposal received from Ed Miller Randy Kondele

(company name) Labanco Drilling Co. Inc. (phone) _____

were: 8 5/8" 157' S.P. cwc w/125 sks. 4 1/2" casing set at 1335' w/400 sks cement.

The above well was washed down to 1335'; Ran 4 1/2" casing. Circulated 400 sks cement.

Perfs at 939' to 1065'. No pipe recovery. Proposal 50 sks Class A Cement and 100 sks 60/40

Poz 6% Gel. Spot with tubing. Circulate cement from top to bottom. Then, squeeze

4 1/2" casing. Load and pressure annulus with cement.

_____ Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00PM Day: 23 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Labanco ordered 50 sks Class A Cement and 100 sks 60/40 Poz
6% Gel. Cement spotted with tubing.

(1) Spotted 50 sks Class A Cement at 1047'; 2. Spotted 100 sks cement at 550'

Cement circulated. Pressured annulus to 400 Psig. Shut in at 400 Psig. Would not take
cement. (Casing had cement top to bottom) Returned with another 50 sks cement.

Squeezed down 4 1/2" casing 50 sks cement. Max pressure 400 Psig. Shut in at 400 Psig.

Remarks: Cemented by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED (1) ~~10/10/88~~ observe this plugging.

DATE 7-25-88

INV. NO. 21632

OR. G. S.

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt