

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00154-00-00
Spot: CSWSWSW Sec/Twnshp/Rge: 31-9S-17W
330 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: WESTHUSIN Well Number: 1
County: ROOKS Total Vertical Depth: 3615 feet

Operator License No.: 8133

Production Casing Size: 5.5 feet: 3595 **\$117.49**

Op Name: HAMMERSCHMIDT, WILLIAM E

Surface Casing Size: 8.625 feet: 200

Address: 904 S SECTION LINE
PLAINVILLE, KS 67663

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/20/2003 10:00 AM

Plug Co. License No.: 8133

Plug Co. Name: HAMMERSCHMIDT, WILLIAM E

Proposal Rcvd. from: WILLIAM E. HAMMERSCH Company: HAMMERSCHMIDT, WILLIAM E Phone: (785) 434-2403

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid Level 250'. PBTD 1230'.
Squeeze job 920' - surface 175 sxs.
LKC Perfs 3338' - 3410'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/20/2003 1:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2000'. Hit small bridge at 1230'.
Allied pumped 300 sxs 60/40 pozmix - 10% gel with 400# hulls.
Pulled to 900'. Allied pumped 30 sxs cement - cement circulated.
PTOH. Squeezed with 20 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Checked backside - pressured to 500#. Prior squeeze job to surface.
Note: Emergency plug orders given while rig over hole.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED
2-24-03
FEB 24 2003

KCC WICHITA

FEB 21 2003

INVOICED

Form CP-2/3

DATE 2-27-03

INV. NO. 2003061229

W. L. HARJMAN #1 WESTHUS IN Ar4 31-9-17W
 SW SW SW
 Contr. H & H GRILLING COMPANY ROOKS County
 E 2118 Comm. Comp. 12-17-48 IP 12 BOPD

Tops	Depth	Datum	Casing
TOP	3045	-927	8" 200 PB 3516
HLEB	3265	-1147	5" 3595 PERF 24 S, 3477-88
LANS	3304	-1186	ACID 2500
SIMP SH	3581	-1463	PMP 20 B0/24 HRS
SIMP DOL	3583	-1465	PMP 12 B0/24 HRS
REW ARB	3613	-1495	
T.O.	3615	-1497	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

