

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

FILED  
FEB 23 1961  
2-23-61  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks \_\_\_\_\_

Location: NE NE SE Sec. 31 Twp. 9 Rge. 17 (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3599

I have this date completed supervision of plugging of:

Lease Name: Ganoung Well No. 1

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 456

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 19 Month 2 Year 61

The above well was plugged as follows:

8 5/8" 157' circulated with cement - 5 1/2" 3592' with 100 sax cement behind.  
Filled with sand to 3580', set 4 sax cement with dump bailer, pulled 2800'  
5 1/2" to 300', circulated hole with heavy mud through 5 1/2" ( 45 sax Gel),  
displaced 20 sax cement through 5 1/2" at 300', heavy mud to 160', displaced  
20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Knight Pulling Co's pump truck.

Signed: *Edwin Perry*  
Conservation Division Agent

Reviewed: *Dyall E. Sharp*  
Field Supervisor

Remarks:

INVOICED  
DATE 3/2/61  
REV. NO 2716-4