

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22561-00-00  
Spot: SWNWSESE Sec/Twnshp/Rge: 24-33S-39W  
850 feet from S Section Line, 1175 feet from E Section Line  
Lease Name: PELAJO Well #: 24 1  
County: STEVENS Total Vertical Depth: 1700 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.

Address: 3817 NW EXPRESSWAY, SUITE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	684		

\$ 55.25

Well Type: GAS *OH KCC REC* UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2006 10:30 PM

Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Revd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SPOT MUD WITH 30 # BBL COTTONSEED HULLS AND COT LINE ROPE TO REGAIN LOST CIRCULATION THRU DRILL PIPE C/O 930'. AT 930' SPOT 100 SX 60/40 POZMIX 6% GEL, 1/8 #/SK FLAKE AND 2 % CC. HOLE CIRCULATED FELL BACK A LITTLE. WAIT 2 HOURS. FILL HOLE WITH MUD. STAGED FULL. AT 710', SPOT 100 SX 60/40 POZMIX 6% GEL, 1/8 # /SK FLAKE. HOLE CIRCULATED. AT 60', SPOT 10 SX 60/40 POZMIX 6% GEL, 1/8 # SK FLAKE. HOLE CIRCULATED. STAYED FULL.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 11/18/2006 3:30 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

SPOT MUD WITH 30 # BBL COTTONSEED HULLS AND COT LINE ROPE TO REGAIN LOST CIRCULATION THRU DRILL PIPE C/O 930'. AT 930' SPOT 100 SX 60/40 POZMIX 6% GEL, 1/8 #/SK FLAKE AND 2 % CC. HOLE CIRCULATED FELL BACK A LITTLE. WAIT 2 HOURS. FILL HOLE WITH MUD. STAGED FULL. AT 710', SPOT 100 SX 60/40 POZMIX 6% GEL, 1/8 # /SK FLAKE. HOLE CIRCULATED. AT 60', SPOT 10 SX 60/40 POZMIX 6% GEL, 1/8 # SK FLAKE. HOLE CIRCULATED. STAYED FULL.

INVOICED  
DATE 12-11-06  
INV. NO. 2007060947

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON

Plugged through: DP

District: 01

Signed

Steve Dummit  
(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 06 2006

KCC WICHITA

*PKT*