

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20118-00-00
Spot: W2E2SE Sec/Twnshp/Rge: 6-14S-19W
1320 feet from S Section Line, 990 feet from E Section Line
Lease Name: IRVIN B Well #: 4
County: ELLIS Total Vertical Depth: 3874 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3865	0	165 SX
SURF	8.625	207	0	w/unknown sxs cmt

\$ 125.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2006 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1314

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perf Tech perfed at 2160' - 1575' - 765' - 250'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2006 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin Drilling Company cleaned hole down to 3857'. RIH with tubing to 2503'.
Quality Well Service rigged to tubing and pumped 200 sxs with 400# hulls mixed in.
Pulled tubing to 1017'. Quality rigged to tubing and pumped 60 sxs with 100# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing and pumped 50 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 350#.
Rigged to 8 5/8" - pressured to 500#.
Backside had cement already in head area.

Perfs:

Top	Bot	Thru	Comments
3865	3875		ARBUCKLE
3586	3750		LKC

INVOICED
DATE 12-11-06
INV. NO. 2007060956

Remarks: QUALITY CEMENTING WELL SERVICE-TICKET #1283.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

DEC 07 2006

KCC WICHITA

Form CP-2/3

DEC 04 2006

Pat

