

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21353-00-00
Spot: NENWNE Sec/Twnshp/Rge: 8-24S-17W
4780 feet from S Section Line, 1820 feet from E Section Line
Lease Name: NIXON Well #: 4-8
County: EDWARDS Total Vertical Depth: 4521 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4517	2200	225 SX
SURF	8.625	313		225 SX

\$ 146.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2006 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MR. ROB LONG Company: _____ Phone: (620) 793-0915

Proposed Plugging Method: SANDED TO 4290' AND 4 SX CMT. WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 340' WITH 40 SX CMT. 4TH PLUG AT 40 WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2006 4:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4290' AND 4 SX CMT. WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 340' WITH 40 SX CMT. 4TH PLUG AT 40 WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4348	4358		

INVOICED

DATE 12-11-06
INV. NO. 2007060948

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
DEC 06 2006
KCC WICHITA

Form CP-2/3