

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21143-00-00
Spot: NWSENE Sec/Twnshp/Rge: 17-24S-17W
1650 feet from N Section Line, 990 feet from E Section Line
Lease Name: LOVETTE Well #: 2-17
County: EDWARDS Total Vertical Depth: 4500 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4493	2100	225 SX
SURF	8.625	265		210 SX

\$ 146.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2006 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MR. ROB LONG Company: _____ Phone: (620) 793-0915

Proposed Plugging Method: PUMPED 30 SX COMMON CMT WITH 500 # HULLS DISPLACED TO 4000'. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2006 12:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 30 SX COMMON CMT WITH 500 # HULLS DISPLACED TO 4000'. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4094	4107		
4084	4087		
4075	4078		

INVOICED
DATE 12-11-06
INV. NO. 2007060948

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED [Signature]
DEC 06 2006
KCC WICHITA

[Handwritten Initials]