

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22771-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 15-24S-15W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BIGGS Well #: 1-15
County: STAFFORD Total Vertical Depth: 4240 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4234	2000	225 SX
SURF	8.625	268		165 SX

\$ 137-80

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/27/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MR. ROB LONG Company: _____ Phone: (620) 793-0915

Proposed Plugging Method: SANDED TO 4000 AND 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASIING WHILE PULLING. 1ST PLUG AT 1000' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2006 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4000' AND 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASIING WHILE PULLING. 1ST PLUG AT 1000' WITH 15 SX GEL AND 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4094	4107		
4084	4087		
4075	4078		
4059			

Remarks: USED 60/40 POZMIX 6% BY COPELAND ACID

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 12-11-06
INV. NO. 2007060948

RECEIVED
DEC 06 2006
KCC WICHITA

Form CP-2/3

[Handwritten signature]