

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20292-00-00  
Spot: E2NE Sec/Twnshp/Rge: 30-21S-17W  
1320 feet from N Section Line, 660 feet from E Section Line  
Lease Name: GORE Well #: 1  
County: PAWNEE Total Vertical Depth: 2060 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 505 S. BROADWAY #200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2059		75 SX
SURF	8.625	276		225 SX

**\$ 66.95**

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2006 12:15 PM  
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC  
Proposal Revd. from: BILL TATRO Company: \_\_\_\_\_ Phone: (620) 727-1948

Proposed Plugging Method: SET CIBP AT 1990' WITH 2 SX CMT. PERFORATED AT 1100'. PUMPED 425 SX DOWN 4 1/2" CASING. POOR CIRCULATION UP 8 5/8" X 4 1/2" CASING. PERFORATED AT 400'. PUMPED 125 SX CMT DOWN 4 1/2". NO CIRCULATION. PUMPED 5 SX CMT DOWN 8 5/8" X 4 1/2" ANNULAS 1000 PSIG MAX-SHUTIN 1000 PSIG

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/24/2006 9:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP AT 1990' WITH 2 SX CMT. PERFORATED AT 1100'. PUMPED 425 SX DOWN 4 1/2" CASING. POOR CIRCULATION UP 8 5/8" X 4 1/2" CASING. PERFORATED AT 400'. PUMPED 125 SX CMT DOWN 4 1/2". NO CIRCULATION. PUMPED 5 SX CMT DOWN 8 5/8" X 4 1/2" ANNULAS 1000 PSIG MAX-SHUTIN 1000 PSIG

Perfs:

Top	Bot	Thru	Comments
2040	2065		

**INVOICED**  
DATE 12-11-06  
INV. NO. 2007060949

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
DEC 06 2006  
KCC WICHITA

FOUR CLERKS

*[Handwritten initials]*