

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20373-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 27-21S-17W
3308 feet from S Section Line, 4791 feet from E Section Line
Lease Name: PHILLIPS Well #: 1
County: PAWNEE Total Vertical Depth: 2056 feet

Operator License No.: 32302

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	760		

Op Name: KEY GAS CORP.

Address: 505 S. BROADWAY #200
WICHITA, KS 67202

\$ 66-82

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/23/2006 9:30 AM

Plug Co. License No.: 99981

Plug Co. Name: COPELAND ACID & CEMENT, INC.

Proposal Rcvd. from: BILL TATRO

Company:

Phone:

Proposed Plugging Method: SET CIBP AT 1985' WITH 2 SX CMT. ON TOP WITH DUMP BAILER. PERFORATED 4 1/2" AT 770' PUMPED 305 SX CMT DOWN 4 1/2 CASING. CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNUALS. CLOSED IN 8 5/8" X 4 1/2" ANNULAS AND PRESSURED UP SYSTEM TO 100 PSI.

Plugging Proposal Received By: JERRY W. STAPLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/23/2006 10:35 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP AT 1985' WITH 2 SX CMT. ON TOP WITH DUMP BAILER. PERFORATED 4 1/2" AT 770' PUMPED 305 SX CMT DOWN 4 1/2 CASING. CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNUALS. CLOSED IN 8 5/8" X 4 1/2" ANNULAS AND PRESSURED UP SYSTEM TO 100 PSI.

Perfs:

Top	Bot	Thru	Comments
2034	2038		

INVOICED
DATE 12-11-06
INV. NO. 2007060949

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
DEC 06 2006
KCC WICHITA

Form CP-2/3

PKT