

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21816-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 5-22S-14W  
5018 feet from S Section Line, 1091 feet from E Section Line  
Lease Name: ESTES A Well #: 6  
County: STAFFORD Total Vertical Depth: 3886 feet

Operator License No.: 5631  
Op Name: LOEWEN OPERATOR, INC.  
Address: 208 S. MAIN PO BOX 335  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3884		475 SX
SURF	8.625	330		330 SX

**\$126.30**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2006 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DOUG LOEWEN Company: \_\_\_\_\_ Phone: (620) 628-4425

Proposed Plugging Method: PUMPED 50 SX OF CEMENT THROUGH TUBING AT 3700'. SET CIBP AT 900'. PRESSURE TESTED 5 1/2" TO 800 PSIG. PERFORATED 5 1/2" AT 825'. PRESSURED 5 1/2" TO 1500 PSIG. NO ENTRY. PRESSURED 8 5/8 X 5 1/2" ANNULAS TO 500 PSIG. NO ENTRY. WELL HAS BEEN SQUEEZED. RAN TUBING TO 899'. CIRCULATED CMT TO SURFACE UP 5 1/2" W/155 X CMT. PULLED TUBING TOPPED OFF WITH 5 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/07/2006 6:05 PM KCC Agent: RICHARD LACEY

**Actual Plugging Report:**

PUMPED 50 SX OF CEMENT THROUGH TUBING AT 3700'. SET CIBP AT 900'. PRESSURE TESTED 5 1/2" TO 800 PSIG. PERFORATED 5 1/2" AT 825'. PRESSURED 5 1/2" TO 1500 PSIG. NO ENTRY. PRESSURED 8 5/8 X 5 1/2" ANNULAS TO 500 PSIG. NO ENTRY. WELL HAS BEEN SQUEEZED. RAN TUBING TO 899'. CIRCULATED CMT TO SURFACE UP 5 1/2" W/155 X CMT. PULLED TUBING TOPPED OFF WITH 5 SX CMT.

**Perfs:**

Top	Bot	Thru	Comments
3860	3862		FP

**INVOICED**  
DATE 12-11-06  
INV. NO. 2007060950

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
DEC 06 2006  
KCC WICHITA

Form CH 2/3  
*[Handwritten initials]*  
*[Handwritten initials]*