

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01514-00-00
API NUMBER NA Drilled 1963

LEASE NAME Mary Dougherty

WELL NUMBER No. 7

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1320 Ft. from S(N) Line of Section (circle one)

2310 Ft. from EW Line of Section (circle one)

LEASE OPERATOR UNREIN OIL CO.

SPOT LOCATION C - W/2 - W/2 - NE/4

ADDRESS 2207 DOWNING ST.

SEC. 13 TWP. 9S S. RGE 17W (E) or (W)

CITY, STATE, ZIP HAYS, KANSAS 67601

COUNTY ROOKS

PHONE#(785) 628-3530 OPERATORS LICENSE NO. 30553

Date Well Completed July 1963

Charater of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced Jan. 14, 1998

Date Plugging Completed Jan. 14, 1998

The plugging proposal was approved on Emergency plugging 1/12/1998 by Carl Goodrow (date)
by Plugging operations witnessed by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation(s) KC & Toronto Depth to Top 3148 Bottom 3381 T.D. 3410 CIBP

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Dakota water sands	Anhydrite	1286' 370'	1320' 1010'	8 5/8"	203'	None
Topeka shale ans	lime	2910	3130	4 1/2"	3465'	None
Lsg. KC and Toronto	lime	3146	3412			
Conglomerate	snd & lime	3424	3450			
Arbuckle	dolomite	3456	TD 3479			

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Cast iron bridge plug @ 3410' No junk in hole, cement down 4 1/2" casing with 235 Sz 60/40 Poz-mix 10% Gel. and 400# cotton seed hulls. (Hole full cement)

Open braden head and squeeze in 25 Sx with 200# Hulls @ 500# and shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO.

License No. NA

Address RUSSELL, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GLEN UNREIN (UNREIN OIL CO.)

STATE OF KANSAS COUNTY OF ROOKS, ss.

CHARLES D. FARR Cons. Eng. (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Charles D. Farr

(Address) 209 W. 33 St. Hays, Ks. 67601

SUBSCRIBED AND SWORN TO before me this 15 day of January, 19 98

Karie L. Younger
Notary Public

My Commission Expires: 7-10-2000



Form CP-4
Revised 12-92

Received
1-20-98
JAN 20 1998