

LEASE NAME Mary Dougherty

WELL NUMBER 9

2970 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 13 TWP. 9 RGE. 17 (E) of (W)

COUNTY Rooks

Date Well Completed 10-23-68

Plugging Commenced 9-14-94

Plugging Completed 9-14-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Harold Krueger Co.

ADDRESS P.O. Box 247, Natoma, KS 67651

PHONE#( 913 ) 885-4701 OPERATORS LICENSE NO. 5769

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-8-94 (date)

by Dennis L. Hamel (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation KC Lime Depth to Top 3196 Bottom 3358 T.D. 3463

Show depth and thickness of all water, oil and gas formations.

3463  
KCC ZAP

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	215'	None
				4 1/2"	3463'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. R.I.H. with perf. tools to perf. casing at 2000' - 1350' 750'. Perf same. Rig up cementers to squeeze 4 1/2" casing as follows: 35 sxs. cement with 200# hulls, followed with 7 sxx gel, followed with 200 sxs. cement with 200# hulls in cement. Max. P.S.I. 400#. 85/8" S.P. Squeezed 50 sxs. cement with 100# hulls. Max. P.S.I. 650#. Job complete.

Name of Plugging Contractor Halliburton Cementing License No. 10-26-94

Address Oberlin, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold Krueger Co.

STATE OF KANSAS COUNTY OF OSBORNE, ss.

Dean Wineland (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Wineland

(Address) 807 6th Natoma, Mo

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1994

Della M. Richmond  
Notary Public

My Commission Expires: 7-22-96  
USE ONLY ONE SIDE OF EACH FORM

DELLA M. RICHMOND  
STATE NOTARY PUBLIC  
OSBORNE COUNTY, KANSAS  
My Appt. Exp. 7-22-96