

15-163-19265-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 13 Twp. 9 Rge. (E) 17 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NE SE

Lease Owner Stearns Petroleum, Inc.

Lease Name Westhusin

Office Address Russell, Kansas

Well No. 1-KCC
af3
12-6-06

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 14 19 49

Application for plugging filed July 14 19 49

Application for plugging approved July 14 19 49

Plugging commenced July 14 19 49

Plugging completed July 14 19 49

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty

Producing formation Depth to top Bottom Total Depth of Well 3446 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	XXXXft 255 ft.	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 250 feet

Bridge at 250 feet. 15 sax cement

Mud to 35 feet

Bridge at 35 feet. 10 sax cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Petroleum, Inc.,
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.

O. G. Stearns (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July 19 49

My commission expires August 17, 1950

22-5133-s 9-48-10M

PLUGGING
FILE SEC 13 T 9 R 17 W
BOOK PAGE 105 LINE 34

Received
B. F. Verman
Notary Public.

15-163-19265-00-00

WESTHUSIN

The SE/4 of Sec. 13-9-17- Rooks County, Kansas
except ~~NE/4~~ of the NE/4 of said SE/4

^{NW}
Elevation: 2022' D. F.

Totco.

Contractor: Stearns Petroleum, Inc.
Commenced: June 29, 1949
Completed: July 14, 1949

45 min. 835'
50 min. 1535'
45 min. 1690'
30 min. 2045'
00 2490'
30 min. 2920'

Casing Record

8 5/8" casing 255' with 125 sx.
cement

WELL LOG

	<u>FROM</u>	<u>TO</u>
Shale	0	95
Shale & shells	95	530
Sand	530	560
Red Shale	560	805
Shale & shells	805	1263
Anhydrite	1263	1300
Shale & shells	1300	1625
Salt	1625	1730
Lime & shale	1730	2920
Lime	2920	3107
Hebner		3107
Lime	3107	3446
Dodge		3127
Lansing		3148
Base Kansas City		3339
Arbuckle		3441
		3446 R. T. D.

STATE OF KANSAS)
(SS
COUNTY OF RUSSELL(

I hereby certify that the above information is true
and correct to the best of my knowledge.

[Signature]

SUBSCRIBED and sworn before me this 15 day of July 1949

[Signature]

Notary Public

My Commission Expires:

August 17, 1950

PLUGGING
REC-13-9-17-1
BOOK PAGE 105-34

RECEIVED
JUL 22 1949