

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: PO Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/02/06 (Date)
by: Darrell Dippman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing/KC Depth to Top: 4057' Bottom: 4337' T.D. 4690'
Conglomerate Sand Depth to Top: 4628' Bottom: 4634' T.D. 4690'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 063-21453 -00 -01
Lease Name: B Ward
Well Number: 1
Spot Location (QQQQ): _____ - NE - NE - NW
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 15 Twp. 11 S. R. 31 East West
County: Gove
Date Well Completed: 11/19/93 1/14/2000
Plugging Commenced: 11/02/06
Plugging Completed: 11/02/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing/KC	oil & water	4057'	4337'	8.625"	209'	0
				4.50"	4687'	0
Conglomerate Sand	oil & water	4628'	4634'			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Pumped 240 sx. of 60/40 Pozmix w/ 10% gel and 600# hulls down 4 1/2" casing. Shut-in pressure = 100#.
Pumped 25 sx. of 60/40 Pozmix w/ 10% gel down 8 5/8" casing at 150 PSI. Shut-in pressure = 50#
Plugging complete @ 10:30 a.m., witnessed and approved by Darrell Dippman w/ KCC.

Name of Plugging Contractor: CO-TOOLS Ritchie Exploration, Inc. License #: 99998 *KCC Per cpz/b PRT*
Address: PO Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of KS. County, Sedgwick, ss.

JOHN NIENBERGER (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) _____



SUBSCRIBED and SWORN TO before me this 1st day of December, 20 06
Debra K Phillips My Commission Expires: 5/4/07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 04 2006
KCC WICHITA *PRT*

