

15-163-19268-00-06


WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Rocks _____ County. Sec. 14 Twp. 9 Rge. 17 (#) _____ (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE., T/4, NE., T/4, NE., T/4.
Lease Owner Harbar Drilling Co., Etal
Lease Name Westhusin Well No. E-1
Office Address 1019 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Rotary Dry Hole
Date well completed 12/2/48 19_____
Application for plugging filed 12/2/48 19_____
Application for plugging approved 12/2/48 19_____
Plugging commenced 12/2/48 19_____
Plugging completed 12/2/48 19_____
Reason for abandonment of well or producing formation No production



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production X 19_____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation None Depth to top X Bottom X Total Depth of Well 3495 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surface sands & soils</u>	<u>Nothing</u>	<u>0</u>	<u>100</u>	<u>8 5/8</u>	<u>98</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from T.D. (3495) to 98 feet and set wood plug and dumped 15 sx. cement on top plug and filled hole with mud from top cement to 20 feet of top set another wooden plug at 20 feet and dumped 10 sx. cement on top plug, filling top surface pipe and bottom cellar.
Cement circulated on surface pipe at time it was set.

RECEIVED
12/10/48
DEC 10 1948
STATE CORPORATION COMMISSION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Harbar Drilling Co.
Address 1019 Central Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

_____ (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Pfeiffer

SUBSCRIBED AND SWORN to before me this 7th day of December, 1948
Roy Gillig (Address)
Notary Public.

My commission expires 9-4-50

PLUGGING
FILE SEC 14 T 9 R 17 W
BOOK PAGE 71 LINE 35

WESTHUSIN #E-1

Rigging up Rotary Tools 11-14-48
 Tearing down Rotary Tools 12-3-48

Ran 5 Jts of 8 5/8" surface pipe.
 Set @ 98 feet and cemented with
 75 sacks of cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	0	100
Shale and redbed	100	680
Shale, sand and redbed	680	1110
Redbed and shale	1110	1295
Anhydrite	1295	1330
Redbed	1330	1350
Anhydrite, shale and bedbed	1350	1570
Shale and salt	1570	1800
Shale	1800	2010
Lime and shale	2010	2090
Shale and shells	2090	2175
Shale and lime	2175	2875
Lime	2875	3015
Lime and shale	3015	3059
Lime	3059	3155
Lime and shale	3155	3193
Lime	3193	3380
Lime and shale	3380	3480
Lime	3480	3500 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct,
 to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 9th day of December, 1948.

My commission expires: March 22, 1952

Henry Kelly
 Notary Public

RECEIVED
 12/10/48
 DEC 10 1948
 STATE REGISTRATION
 COMMISSION
 KANSAS

PLUGGING
 FILE SEC-1419-R170
 STAMP PAGE 71 LINE 35