

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-163-22,175-00-00

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME EADS

WELL NUMBER 1

SPOT LOCATION SE NW SE

LEASE OPERATOR Raymond Oil Co., Inc.

SEC. 15 TWP. 9 RGE. 17 (E) OR (W)

ADDRESS One Main Place Wichita, KS 67202

COUNTY Rooks

PHONE #(316) 267-4214 OPERATORS LICENSE NO. 5046

DATE WELL COMPLETED 10-25-83

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 10-26-83

PLUGGING COMPLETED 10-26-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Carl Goodrow

Is ACC-1 FILED? operator to be filed by operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3520

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 1325' w/20 sacks cement thru drill pipe

Next Plug: @ 800' w/100 sacks " " " "

Next Plug: @ 260' w/40 sacks " " " "

Top Plug: @ 40' w/1/2 sacks hulls & 10 sacks cement
10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE No. 5929
ADDRESS Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Leonard Williamson

(ADDRESS) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 31 DAY OF Oct, 1983

Dorothy M Hague
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1983
WICHITA, KANSAS

FORM CP-4
REVISED 06-83

15-163-22175-00-00

DRILLER'S WELL LOG

DATE COMMENCED: October 19, 1983
DATE COMPLETED: October 26, 1983

Raymond Oil Co., Inc.
EADS #1
SE NW SE
Sec. 15, T9S, R17W
Rooks County, Ks.

ELEVATION: 2059 K.B.

0 - 1320' Surface Soil, Shale Shells
1320 - 1357' Anhydrite
1357 - 2886' Lime & Shale
2886 - 2936' Lime
2936 - 2956' Shale & Sand
2956 - 3176' Lime
3176 - 3180' Shale
3180 - 3197' Lime & Shale
3197 - 3455' Lime
3455 - 3520' Shale, Lime, Chert, Sand
3520' RTD

FORMATION DATA

Anhydrite 1320'
Howard 2886'
Severy 2936'
Topeka 2956'
Heebner 3176'
Toronto 3197'
Kansas City 3216'
Base K.C. 3455'
Conglomerate 3499'
RTD 3520'

Surface Piper: Set new 8-5/8"
20' pipe 16 258' w/160 sacks
60/40 pozmix 28 gal 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 1st day of November 1983.

My Comm. Expires:

4-29-86

Dorothy M. Hague
Notary Public