

15-163-20149-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 15 Twp. 9S Rge. (E)/17 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 SW/4
Lease Owner Abercrombie Drilling, Inc.
Lease Name WATKINS Well No. 1
Office Address 801 Union Center; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 5, 19 68
Application for plugging filed (verbally) November 5, 19 68
Application for plugging approved (verbally) November 5, 19 68
Plugging commenced November 5, 19 68
Plugging completed November 5, 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3572 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug @880' w/50 sx. cement;
Set 2nd plug @245' w/20 sx. cement;
Set top plug @ 40' w/10 sx. cement.
Job was completed 3:00 p.m., 11-5-68.

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address (Office) 801 Union Center; Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

A. L. Abercrombie (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie, President
801 Union Center; Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 6th day of November, 19 68.

Notary Public
Sue J. Blunck, Notary Public.
My commission expires July 15, 1972



CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.
CONTRACTOR: Abercrombie Drilling, Inc.
LEASE: WATKINS #1
LOCATION: SE/4 NE/4 SW/4, Sec. 15-9S-17W
Rooks County, Kansas
GEOLOGIST: Jack K. Wharton
COMMENCED: October 29, 1968
COMPLETED: November 5, 1968

0	40	Rock
40	225	Clay & Sand Streaks
225	715	Shale
715	755	Sand Streaks & Shale
755	1050	Sand
1050	1373	Shale
1373	1410	Anhydrite
1410	1750	Shale
1750	2287	Shale & Lime
2287	3085	Lime & Shale
3085	3500	Lime
3500	3510	Lime & Conglomerate Sand
3510	3550	Lime & Shale
3550	3572	Dolomite
	3572	Rotary Total Depth

Drilled 260' of 9" surface hole and set 7" casing @252' w/75 sx. Sunset cement.
Cement circulated. Plug was down 4:45 p.m., 10-29-68.
Dry & Abandoned

FORMATION SAMPLE TOPS


ELEVATION

T/Anhydrite	1373	(+ 731)	2104 K. B.
Heebner	3220	(-1116)	2102 D. F.
Toronto	3240	(-1136)	2096 G. L.
Lansing	3262	(-1158)	
Base/K.C.	3498	(-1394)	
Arbuckle	3542	(-1438)	
Rotary T.D.	3572	(-1468)	


RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1968
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

A. L. Abercrombie, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WATKINS #1, located in the SE/4 NE/4 SW/4, Sec. 15-9S-17W, Rooks County, Kansas.


A. L. Abercrombie
President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, as of this 6th day of November, 1968.


Sue J. Blunck
Notary Public

My Commission Expires:

July 15, 1972

