

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 15 Twp. 9 Rge. 17W (S/2 NW/4) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW NW

Lease Owner Raymond & Lebow Drilling Company

Lease Name Carmichael Well No. 1

Office Address 202 Bissantz Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 21, 1949 19

Application for plugging filed May 4, 1950 19

Application for plugging approved May 4, 1950 19

Plugging commenced May 17, 1950 19

Plugging completed May 31, 1950 19

Reason for abandonment of well or producing formation unable to make a producing well

If a producing well is abandoned, date of last production April, 1950 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top 3413 Bottom 3519 Total Depth of Well 3519 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	158'	
				5-1/2"	3519'	900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8-5/8" set at 158 feet circulated with cement. 5-1/2 " at 3518 feet with 100 sacks cement behind. Filled with chat to 3325 feet; run 5 sacks of cement with dump bailer. Pumped in 140 sacks mud, 4 bales Palcoseal and 50 sacks hulls. Pulled 900 feet of 5-1/2" Set wood plug at 155 feet/ rock bridge and 15 sacks cement. Heavy mud to 35 feet; set rock bridge and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Raymond & Lebow Drilling Company, Address 202 Bissantz Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Francis M. Raymond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Francis M. Raymond
202 Bissantz Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 13th day of JUNE 1950

My commission expires MAY-18-1952

Notary Public
6/14/50
JUN 14 1950

PLUGGING
FILE SEC 15 T 9 R 17
BOOK PAGE 4 LINE 16

STATE CORPORATION COMMISSION
KANSAS

Raymond & Lebow Drilling Co. Inc.
 202 Bessantz Bldg.
 Wichita, Kansas

KCC 2AP
 NWSW NW
~~S/2 NW/4~~
 Sec. 15-9S-17W
 Rooks County, Kansas

Carmichael No. 1

Comm. 5-11-1949
 Comp. 5-21-49

Total Depth 3519

	Casing 8 5/8"	158' Cem.	
	5 1/2"	3519' Cem.	
Surface Clay	0	30	
Gravel & Shale	30	90	
Shale	90	135	
Shale & Sand	135	159	Set and Ce. Surface Pipe
Shale	159	610	
Sand & Gravel	610	720	
Red Bed & Shale	720	980	
Shale	980	1340	
Lime Shells	1340	1360	
Anhydrite	1360	1395	
Shale & Shells	1395	1850	
Shale & Lime Shells	1850	1940	
Lime	1940	1965	
Shale & Shells	1965	2070	
Lime & Shale	2070	2210	
Lime	2210	2260	
Shale	2260	2320	
Shale, Lime & Shells	2320	2460	
Lime	2460	2550	
Shale & Lime Strks	2550	2625	
Shale & Lime	2625	2655	
Lime	2655	2800	
Lime & Shale	2800	3105	
Lime (Topeka)	3105	3180	
Lime & Shale	3180	3210	
Lime	3210	3280	
Cherty Lime	3280	3308	
Lime	3308	3365	
Lime & Shale	3365	3413	
Lime	3413	3519	Set and cemented 5 1/2 Casing

RECEIVED
 MAY 4 1950
 STATE OF KANSAS
 COUNTY OF SEDGWICK
 Set and cemented 5 1/2 Casing

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RAYMOND & LEBOW DRILLING COMPANY INC.

BY *Francis M. Raymond*

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS

Subscribed and sworn to before me, a notary public, in and for said County and State this 3rd. day of May 1950

My commission expires May 18, 1952

Glenn W. [Signature]
 Notary Public

