

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Geist Oil Operations

Address: 807 Grant Victoria, KS 67671

Phone: (785) 735-7020 Operator License #: 30680

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/20/06 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Lansing K. City Depth to Top: 3580' Bottom: 3646' T.D. 3690'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-02885-00-02

Lease Name: Younger & Per CP213PA

Well Number: #6

Spot Location (QQQQ): E 1/2 - NE - SW - SE

990 Feet from ☐ North / ☒ South Section Line

990 Feet from ☐ East / ☒ West Section Line

Sec. 25 Twp. 13 S. R. 20 ☒ East ☒ West

County: Ellis

Date Well Completed: 3-17/58 *original date*

Plugging Commenced: 11/27/06

Plugging Completed: 11/27/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Lansing K/C</u>	<u>oil</u>	<u>0</u>	<u>250'</u>	<u>8 5/8</u>	<u>250'</u>	<u>NONE</u>
		<u>0</u>	<u>3804'</u>	<u>5 1/2</u>	<u>3804'</u>	<u>NONE</u>
		<u>0</u>	<u>3562'</u>	<u>4 1/2</u>	<u>3562'</u>	<u>NONE</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied on Surface Pumped H₂O & Pressured up & held press. Tied on 4 1/2" Casing
mixed Cement, with Hulls. mixed 190 sks 60-40 cement with 600 lbs
Hulls & Filled with Cement. max Press 500psi & Shut in w/ 500psi held
press. Let well set w/ 500psi on & Broke Pump Truck Down.


Name of Plugging Contractor: Allied Cementing License #: 99996

Address: P.O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Geist Oil Operations

State of KANSAS County, Ellis, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) Bill Geist

(Address) 807 Grant Victoria, KS 67671

SUBSCRIBED and SWORN TO before me this 4th day of December, 2006

Sheila M. Pfannenstiel My Commission Expires: Nov 2, 2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 08 2006
KCC WICHITA