

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Exxon Mobil Oil Corporation
Address: PO Box 4358 Houston TX 77210
Phone: (281) 364 5073 Operator License #: 5208
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-19-06 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2967' Bottom: 3042' T.D. 3160'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-20633-00-00
Lease Name: Dorth-Ehrhardt Unit
Well Number: 1 Ehrhardt
Spot Location (QQQQ): SE - SE - NW-NW
4030 Feet from North / South Section Line
4030 Feet from East / West Section Line
Sec. 11 Twp. 35 S. R. 39 East West
County: Stevens
Date Well Completed: 3-12-83
Plugging Commenced: 10-23-06
Plugging Completed: 10-23-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	<u>591</u>	<u>8 5/8</u>	<u>591</u>	-
production		0	<u>3160'</u>	<u>5 1/2</u>	<u>3160</u>	<u>-580' pjt</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5 1/2 was cmted to surface. Mixed 400 lb. hulls & 25 sx cmt. to plug perf's from 2967 to 2767, 45 bbls mud to 640, mixed 80 sx cmt 640 to 0. Mixed 20 sx down annulus from 120 to 0 Cut off 8 5/8 & 5 1/2 & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: EXXON MOBIL PRID Co
State of KANSAS County, STEVENS, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 14 2006
CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC, State of Kansas
DORETTA L. DELAY
My Appt. Exp. 12-27-08

(Signature) RB Jew
(Address) 200 W 4th HUGOTON KS 67951

SUBSCRIBED and SWORN TO before me this 16 day of November, 2006
Doretta L. Delay My Commission Expires: 12-27-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

regulatory contact: Jacqueline Davis

12/13/06

281-654-1913

pjt