

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/25/06 (Date)
by: Dave Williams Jay Pfeifer *KCC PCT per CPA/3* (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LKC Depth to Top: 3334 Bottom: 3490 T.D. _____
Arbuckle Depth to Top: 3602 Bottom: 3648 T.D. 3648
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-97-593-00-00 *05299*
Lease Name: Hauser A
Well Number: #5
Spot Location (QQQQ): NE NE
2310' Feet from North / South Section Line
2310' 2170' Feet from East / West Section Line
Sec. 34 Twp. 11 S. R. 17 East West
County: Ellis
Date Well Completed: 12/14/51
Plugging Commenced: 11/6/06
Plugging Completed: 11/6/06

KCC PCT per CPA/3 12/14/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	277'	
				5-1/2	3602'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1925'; 1373' and 800'. TIH w/2 7/8" workstring to 3500'. Spotted 140 sx 60/40 poz w/6% gel and 600# hulls. Pulled tubing to 1500' FS. Circulated cement to surface w/120 sx. TOH w/tubing. Filled 5 1/2" w/80 sx cement. Pressured 8 5/8" to 1500#. Approved by Jay Pfeifer w/KCC.

Name of Plugging Contractor: Smoky Hills Well Service *KCC PCT per CPA/3*
Allied Cementing Co., Inc. License #: 32452
Address: P.O. Box 31, Russell, KS 67665-0031
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss. Pat Canaday
Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


RECEIVED
DEC 05 2006
KCC WICHITA

(Signature) *Pat Canaday*
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 1st day of December

Michelle D. Henning
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL RECORD

Company Cities Service Oil Co. Well No. 5 Farm Hauser
 Location 330' South and 330' West of Center Sec. 34 T. 11 R. 17W
 Elevation 2108 (2106 Gr.) County Ellis State Kansas
 Drlg. Comm. November 28, 1951 Contractor Lohmarn-Johnson Drilling Co., Inc.
 Drlg. Comp. December 14, 1951 Acid 1000 gals. 12-15-51
 T. D. 3610' Initial Prod. Pumped 163 oil, 4 1/2 water, 24 hrs. (12-18-51)

CASING RECORD:

8-5/8" @ 277' cen. 150 sz cement
 5-1/2" @ 3602' cen. 150 sz cement

FORMATION RECORD:

shale	0-70
sand & shale	277
shale	360
shale & shells	600
sand & shale	970
shale & red bed	1065
shale & shells	1320
anhydrite	1354
shale & shells	2056
shale	2212
shale & shells	2439
shale & lime	2640
lime & shale	2913
shale	3077
lime & shale	3379
lime	3604
lime	3604 RTD = 3607 SIM
lime	3610 T. P.

Drill stem test 3417-28, open 1 hour,
 recovered 40' oil-cut mud; B. H. P.
 800 # in 15 mins.

Corr. Heetner	3292'
Corr. Dodge	3313'
Corr. Lansing	3338'
Corr. Simpson Shale	3584'
Corr. Arbuckle	3602'
Penetration	8'
Total Depth	3610'

Fillup:

30' oil in 1 hr.
 100' oil in 3 hrs.
 125' oil in 5 hrs.
 200' oil in 13 hrs.

SLOPE TESTS (ACID BOTTLE):

500'	0°
1000'	0°
1500'	0°
2000'	0°
2500'	0°
3000'	0°

7-7/8" rotary hole.

RECEIVED
 DEC 05 2006
 KCC WICHITA

ALLIED CEMENTING CO., INC.

22045

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russel

DATE <u>11-6-06</u>	SEC <u>34</u>	TWP. <u>11</u>	RANGE <u>17</u>	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>9:30 AM</u>	JOB START <u>10:00 AM</u>	JOB FINISH <u>1:30 PM</u>
LEASE <u>Hauser</u>	WELL # <u>5</u>	LOCATION <u>Codell RVR RD. JCT 3 S.</u>		COUNTY <u>ELLIS</u>	STATE <u>KANSAS</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1 W INTO</u>			

CONTRACTOR Smoky Hill Well Serv OWNER

TYPE OF JOB PLUG ABANDONED well

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH 3603

TUBING SIZE 2 7/8 DEPTH 3500

DRILL PIPE _____ DEPTH _____

TOOL 8 5/8 SURFACE DEPTH 277'

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT (USED 340 SK)

AMOUNT ORDERED 400 SK 60/40 GEL

600 # HULLS

COMMON	<u>204</u>	@	<u>10.65</u>	<u>2172.60</u>
POZMIX	<u>136</u>	@	<u>5.80</u>	<u>788.80</u>
GEL	<u>30 SK</u>	@	<u>16.65</u>	<u>499.50</u>
CHLORIDE		@		
ASC		@		
<u>Hull's</u>	<u>6 SK</u>	@	<u>25.50</u>	<u>153.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>421</u>	TOTAL SK @	<u>1.90</u>	<u>799.90</u>
MILEAGE	<u>33 Ton Mile</u>	@	<u>.094</u>	<u>1250.30</u>
TOTAL				<u>5664.70</u>

EQUIPMENT

PUMP TRUCK CEMENTER Glenn

398 HELPER Gary

BULK TRUCK

396 DRIVER Bob

BULK TRUCK

_____ DRIVER _____

REMARKS:

Ran Tubing To 3500' - Spot 140 SK Cement w/ 600 # HULLS, Pull up To 1500' + Circ. Cement To Surface w/ 120 SK. Hooked UP To 5 1/2 csg. w/ Swage & Squeezed IN ANOTHER 60 SK @ 100 # max PSI. Took OFF Swage & CAPPED OFF w/ 20 SK 8 5/8 COULDN'T Pump INTO @ 800#.

THANKS!

CHARGE TO: Vess Oil Corp.

STREET _____

CITY _____ STATE _____ ZIP _____

KCC - Jay Pfeifer
ON LOCATION

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 955.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 33 @ 6.00 198.00

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

6135.46

TOTAL 1153.00

~~NO TAX~~

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

TAX: _____

TOTAL CHARGE DEC 05 2006

DISCOUNT KCC WICHITA PAID IN 30 DAYS

PRINTED NAME _____