

\*Corrected Surmise # & date

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-00009-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 6-14S-19W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: LV IRVIN Well #: 1  
County: ELLIS Total Vertical Depth: 3883 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3878	0	w/unknown sxs cmt
SURF	8.625	192	0	W/100 SXS CMT \$ 126.20

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2006 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEVIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel and 800# hulls.  
Casing leak at 1615' - 1677'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/16/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 2150' - 1550' - 810' - 240'.  
TIH with tubing to 2500' - mixed and pumped 180 sxs with 500# hulls.  
Pulled up to 1000' - circulated cement with 40 sxs and 200# hulls.  
POOH. Swaged onto 5 1/2" and circulated cement up 8 5/8" with 40 sxs.  
Hole full of cement.

INVOICED  
DATE 12-4-06 12/8/06  
INV. NO. 2007060902  
2007060940

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

ND

Signed

Jay Pfeifer

(TECHNICIAN)

NOV 29 2006

RECEIVED  
NOV 30 2006  
KCC WICHITA

Form CP-2/3

PKT