

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20632-00-0001  
Spot: NWNENW Sec/Twnshp/Rge: 23-29S-41W  
330 feet from N Section Line, 1680 feet from W Section Line  
Lease Name: KENDRICK Well #: 23-1  
County: STANTON Total Vertical Depth: 5650 feet

Operator License No.: 33002  
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP  
Address: ATTN: REGULATORY GROUP PO BO  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	5530	635	
SURF	8.625	1677		550 SX

\$ 183.63

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2006 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: ROGER NORTHCUTT Company: \_\_\_\_\_ Phone: (620) 492-1435

Proposed Plugging Method: 250 # HULLS AND 25 SX CMT PORTLAND COMMON 5500'. 86 BBL MUD SPACER. 25 SX PORTLAND COMMON C/O 1700'. FILL HOLE WITH MUD AND PRESSURE TO 500 #. SHOOT CSG C/O 635'. 50 SX PORTLAND COMMON C/O 630'. FULL RETURNS. 10 SX PORTLAND COMMON C/O 40'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2006 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

250 # HULLS AND 25 SX CMT PORTLAND COMMON TO 5500'. 86 BBL MUD SPACER. 25 SX PORTLAND COMMON C/O 1700'. FILL HOLE WITH MUD AND PRESSURE TO 500 #. SHOOT CSG C/O 635'. 50 SX PORTLAND COMMON C/O 630'. FULL RETURNS. 10 SX PORTLAND COMMON C/O 40'.

Perfs:

Top	Bot	Thru	Comments
5430	5464		

**INVOICED**  
DATE 12-14-06  
INV. NO. 2007060975

Remarks: USED PORTLAND COMMON BY SARGENT AND HORTON. RECOVERED 635' OF 5.5 CASING.

Plugged through: CSG

District: 01

Signed

Steve R. Hunt  
(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 06 2006

KCC WICHITA

PET