

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24206-00-00
Spot: SWNW Sec/Twnshp/Rge: 25-22S-20E
1865 feet from N Section Line, 651 feet from W Section Line
Lease Name: KINCAID Well #: 1-25-22-20
County: ANDERSON Total Vertical Depth: 1160 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1153		205 SX
SURF	8.625	22		4 SX

\$ 37.70

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/12/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT W/ 0.5 SXS COTTON SEED HULLS FROM PBTD TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2006 10:45 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

Run 2 3/8 inch tubing to PBTD (1153 feet) and circulate 125 sacks 60/40 Class A/Pozimix cement with half sack cotton seed hulls from PBTD to 4 feet below ground level. Cut casing and weld steel plate 4 feet below ground level. Grade surface level.

Perfs:

RECEIVED
KCC DISTRICT #3

AUG 15 2006 LS

CHANUTE, KS

RECEIVED
DEC 11 2006
KCC WICHITA

INVOICED
DATE 12-14-06
INV. NO. 2007060977

Remarks:

Plugged through: TBG

District: 03

Signed _____

Levi Short

(TECHNICIAN)

PKT