

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24210-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 10-22S-21E  
2310 feet from S Section Line, 2260 feet from E Section Line  
Lease Name: KINCAID Well #: 1-10-22-21  
County: ANDERSON Total Vertical Depth: 986 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	980		170 SX
SURF	8.625	24		4 SX

\$ 35.00

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT W/ 0.5 SX COTTON SEED HULLS FROM PBTD TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/13/2006 12:30 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

Run 2 3/8 inch tubing to PBTD (980 feet) and circulate 120 sacks 60/40 Class A/Pozimix cement with half sack cotton seed hulls from PBTD to 4 feet below ground level. Cut casing and weld steel plate 4 feet below ground level. Grade surface level.

Perfs:

RECEIVED  
KCC DISTRICT #3

AUG 8 2006

CHANUTE, KS

LS

INVOICED

DATE 12-14-06

INV. NO. 2007060977

RECEIVED

DEC 11 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Levi Short

(TECHNICIAN)

PCT