

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24216-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 24-20S-19E
660 feet from N Section Line, 330 feet from W Section Line
Lease Name: ROGERS Well #: 24-11
County: ANDERSON Total Vertical Depth: 1237 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1230		165 SX
SURF	8.625	22		4 SX

\$ 40.20

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Revd. from: LARRY BRYANT Company: TRACKER RESOURCE DEVELOPM Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 950'; CIRCULATE 9.5 PPG BENTONITE MUD FROM 950' TO 150'; CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 150' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: FRANK GUILFOYLE WitnessType: NONE
Date/Time Plugging Completed: 06/07/2006 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

Circulate 60/40 class A/Pozmix cement with 0.5 sacks cotton seed hulls from 1,221 feet to 950 feet. Circulate 9.5 ppg bentonite mud from 950 to 150 feet. Circulate 60/40 class A/Pozmix cement from 150 to 4 feet below ground level. Cut casing and weld steel plate 4 feet below ground level then grade surface level.

Perfs:

RECEIVED
KCC DISTRICT #3

JUL 18 2006

CHANUTE, KS

INVOICED
DATE 12-14-06
INV. NO. 2007060977


RECEIVED
DEC 11 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed



(TECHNICIAN)