

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24241-00-00
Spot: NESENE SW Sec/Twnshp/Rge: 26-19S-19E
1700 feet from S Section Line, 2400 feet from W Section Line
Lease Name: GRETENCORD Well #: 26-23
County: ANDERSON Total Vertical Depth: 1215 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1224		165 SX CMT
SURF	8.625	20		4 SX CMT

\$ 39.49

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/14/2006 11:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 700';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: JOHN ALMOND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2006 12:30 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

Run 2 3/8 inch tubing to PBTD (1192 feet) and circulate 125 sacks 60/40 Class A/Pozimix cement with half sack cotton seed hulls from PBTD to 4 feet below ground level. Cut casing and weld steel plate 4 feet below ground level. Grade surface level.

RECEIVED
KCC DISTRICT #3
AUG 21 2006 LS
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1146	1148		
1140	1142		
1133	1136		
1127	1130		
1093	1095		
920	922		
913	915		
891	893		
882	884		
858	860		
843	845		

RECEIVED
DEC 11 2006
KCC WICHITA

Remarks:
Plugged through: TBG

INVOICED
DATE 12-14-06
INV. NO. 2007060977

District: 03

Signed Levi Short
(TECHNICIAN)

PKT