

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19381-00-00

Spot: SESWSNW

Sec/Twnshp/Rge: 28-30S-16E

2668 feet from S Section Line, 3460 feet from E Section Line

Lease Name: JONES

Well #: 3

County: WILSON

Total Vertical Depth: 800 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	775		775' is an estimate
PROD	5.5	800		800' is estimate
SURF	10	20		

\$35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/27/2004 8:00 AM

Plug Co. License No.: 33422

Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE

Proposal Rcvd. from: RICK HOUSEL

Company: HOUSEL, RICK DBA RICK'S WELL Phone: (620) 336-2944

Proposed
Plugging
Method:

Run cement strings down annular spaces and fill from bottom to top with portland cement.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 03/28/2005 12:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 0.5 inch plastic cement string was lowered down the annular space between the 2 inch pipe and 5.5 inch pipe to 500 ft. A 1.0 inch cement string was lowered down the inside of the 2 inch pipe to 775 ft. A 1.0 inch cement string was lowered down the outside of the 5.5 inch pipe to 250 ft. The well was filled from bottom to top thru these cement strings. A total of 127 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

DEC 4 2006

AMB

CHANUTE, KS

INVOICED

DATE 12-14-06

INV. NO. 2007060969

RECEIVED
DEC 11 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)

PCT