

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20392-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 5-11S-32W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HEYEN Well #: 2
County: LOGAN Total Vertical Depth: 4700 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4698	0	w/250 sxs cmt
SURF	8.625	299	0	w/195 sxs cmt

\$ 152.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2006 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel and 600# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2006 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 299' w/195 sxs cmt.
4 1/2" production casing set at 4698' w/250 sxs cmt.
Port collar set at 2562' w/525 sxs. PBTD 4659'.
Production casing has holes.
Ran tubing to 2500' - pumped 100 sxs cement with 375# hulls.
Pulled tubing to 1200' - pumped 125 sxs cement 200# hulls - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 28 sxs cement.
Max. P.S.I. 500#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 2 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
4208	4213		
3242	4238		

INVOICED

DATE 12-14-06
INV. NO. 2007060970

RECEIVED
DEC 11 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC. TICKET#10,787.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

DEC 04 2006

PKT

GRUSS PETROLEUM
 MANAGEMENT, INC.
 900 BLDG. OF THE SOUTHWEST #2 HEYEN
 MIDLAND, TX 79701


5-11-32W
 C S/2 SW NW

CONTR BEREDCO, INC.

CTY LOGAN

GEOL STEVE MURPHY

FIELD U-PAC SO. EXT
 (1/8 N)



ELV 3093 KB SPD 8/7/85 CARD ISSUED 3/20/86 IP P 119 B0 & 5 BWPD
3088 GL DRLG COMP 8/17/85 LKC 4208-4242 OA

LOG	Tops	Depth/Datum	
ANH	2592+ 501	API 15-109-20,392
HEEB	4020- 927	8 5/8 " 299 / 195SX, 4 1/2 " 4698 / 250SX, MULT STAGE COL-
LANS A	4059- 966	LAR AT 2562 / 525SX
BKC	4338-1245	DST (1) 4086-4105 (LKC B) / 45-30-60-45, REC 339' MCW, SIP
MARM	4404-1311	1215-1215#, FP 23-69 / 81-161#, HP 2102-2097#, BHT 108°
CHER SH	4558-1465	DST (2) 4125-4160 (LKC B) / 30-60-45-90, REC 432' MCW, SIP
JOHN ZN	4601-1508	1283-1283#, FP 46-127 / 150-219#, HP 2136-2113#, BHT 118°
MISS	4656-1563	DST (3) 4186-4225 (LKC H) / 30-60-45-60, 465' GIP, REC 960'
PBTD	4659-1566	M & GCO, SIP 1249-1237#, FP 69-207 / 253-392#, HP 2136-
RTD	4700-1607	2113#, BHT 116°
			DST (4) 4235-4250 (LKC I) / 30-60-45-90, 837' GIP, REC 681'
			MC GSY OIL, SIP 1237-1215#, FP 46-115 / 150-253#, HP 2147-
			2124#, BHT 118°
			DST (5) 4254-4275 (LKC J) / 30-60-30-60, REC 10', SIP 35-
			NOTE: CORRECTION: 8/20/85 - ORIGINALLY FIRST REPORTED AS
			#1 'A' E. HEYEN

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.

(over)

GRUSS PETROLEUM
 MANAGEMENT, INC.

#2 HEYEN

5-11-32W
 C S/2 SW NW

30#, FP 35-35 / 35-35#, HP 2714-2714#, BHT 118°
 DST (6) 4283-4303 (LKC K) / 30-60-45-90, 372' GIP, REC 392' G & OCMW, SIP 1237-1226#, FP 23-140 /
 127-207#, HP 2136-2113#
 DST (7) 4311-4325 (LKC L) / 30-60-45-90, REC 10' DM, SIP 23-23#, FP 23-23 / 23-23#, HP 2158-2136#
 DST (8) 4595-4635 (JOHN ZN) / 30-60-45-90, 651' GIP, REC 299' MC GSY OIL, SIP 1126-1112#, FP 46-81 /
 92-138#, HP 2307-2385#
 MICT - CO, PF (LKC I) 4238-4242, W / 3 SPF, AC 420 GAL (NEA), SWB DWN, GSO, PF (LKC) 4208-4213, W / 3
 SPF, AC 525 GAL (NEA), SWB DWN, GSO, SET 2 3/8 " TBG AT 4473', POP, P 119 B0 & 5 BWPD, 9/19/85