

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20374-00-00
Spot: S2N2SW Sec/Twnshp/Rge: 31-10S-31W
1650 feet from S Section Line, 3960 feet from E Section Line
Lease Name: MOORHOUS Well #: 5-85
County: THOMAS Total Vertical Depth: 4700 feet

Operator License No.: ~~4058~~ ⁸⁹⁹⁶ *mid continent resources, inc*
Op Name: AMERICAN WARRIOR, INC. *per operator goe*
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4698	0	725 SX
SURF	8.625	305	0	225 SX

\$ 152.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2006 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: 1st. - Ordered out 170 sxs Swift Multi-Density Cement with 500# hulls.
2nd. - Ordered out 150 sxs Swift Multi-Density Cement with 500# hulls.
DV tool at 2576' w/550 sxs. Casing collapsed at 3600'. Decided to P/A.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2006 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 20 sxs Swift Multi-Density neat, followed with 150 sxs with 500# hulls - no pressure.
Well on vacuum. Shut in. Waited 2 hours on more cement.
Cement at 2400'. Swift pumped 85 sxs with 400# hulls.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4270	4280		
4115	4119		

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

INVOICED

DATE 12-14-06

INV. NO. 2007060928

RECEIVED
DEC 11 2006
KCC WICHITA

District: 04

Signed

Richard Williams

(TECHNICIAN)

DEC 07 2006

PK


REPLACEMENT CARD

MID CONTINENT RESOURCES, INC. 31-10-31W
 2805 BENTBAY CIRCLE #5-85 MOORHOUS C S/2 N/2 SW
 WICHITA, KS. 67204

CONTR MURFIN DRILLING CTY THOMAS

GEOL DON RIDER FIELD CAMPUS NO.

ELV 3037 KB SPD 11/5/85 CARD ISSUED 2/20/86 IP P 50 BO & 50 BWPD
 3032 GL DRLG COMP 11/11/85 KC 4115-4119
 API 15-193-20,374



LOG	Top	Depth/Datum
ANH	2556 + 481
TOP	3775- 738
HEEB	3996- 959
LANS	4035- 998
BKC	4314-1277
MARM	4343-1306
CHER	4498-1461
MISS	4634-1597
PBTD	4260-1223
RTD	4700-1663

8 5/8 " 305 / 225 SX, 4 1/2 " 4698 / 500 SX, DV TOOL AT 2576
 / 550 SX
 NO CORES OR DSTS
 MICT - CO, PF (CHER) 4591-4597, W / 4 SPF, AC 250 GAL DIE-
 SEL FLUSH W / OIL, SWB DWN, NON-COMMERCIAL, PF (CHER)
 4598-4608, W / 2 SPF, AC 500 GAL (15% INS) & CLAY STAB
 (AMT NA), SWB DWN, NON-COMMERCIAL, PF (LKC) 4270-4280,
 W / 2 SPF, SWB DWN, NON-COMMERCIAL, PF (KC) 4115-4119,
 W / 4 SPF, AC 500 GAL (15% MA), SWB DWN, GSO, SET 2 3/8 "
 TBG AT 4240, POP, P 50 BO & 50 BWPD, 11/29/85

INFO RELEASED: 3/26/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS