

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22379-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 5-21S-10W
2663 feet from S Section Line, 4617 feet from E Section Line
Lease Name: SCOTT A Well #: 1-5
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3300		
PROD	4.5	3472		200 SX
SURF	8.625	202		225 SX

\$ 112.13

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2006 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 21 2006
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/02/2006 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Ran tubing to 1500'. Encountered cement; Acid Services' 9/21/2000 cement ticket indicated well had been squeezed probably for re-completion into shallow gas zone. Perforated @ 1250', 850', and 255'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 255' and circulated cement to surface. Connected on to surface casing and pumped 50 sacks of cement to ensure backside had sufficient cement.

60/40 posmix with 4% gel

Quality Well #1147

Perfs:

Top	Bot	Thru	Comments
3314	3316		
3310	3312		
3121	3126		

INVOICED
DATE 12-15-06
INV. NO. 2007060988

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED Form CP-2/3
DEC 14 2006
KCC WICHITA

PKG