

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21112-00-00
Spot: NENENW Sec/Twnshp/Rge: 20-12S-17W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SCHMEIDLER Well #: 4
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 33810
Op Name: WALCHER OIL, LC
Address: 150 N. MAIN, STE 809
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1393		300 SX
PROD	5.5	3724	0	100 SX CMT. \$121.23
SURF	8.625	253	0	150 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2006 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DAVE HEIN Company: WALCHER OIL, LC Phone: (316) 267-1611

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls,
DV at 1393' set with 300 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hooked up to the annulus - instant 300#.
Swaged onto 5 1/2" - mixed and pumped 300 sxs with 500# hulls.
S.I.P. 50#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

INVOICED
DATE 12-14-06
INV. NO. 2007060980

RECEIVED
DEC 11 2006
KCC WICHITA

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

DEC 07 2006

PCT

DRILLER PROD. CO., INC.
 120 N. MARKET, WICHITA, KS.

#4 SCHMEIDLER

20-12-17W
 NE NE NW

CONTR DUKE DRILLING CO. CTY ELLIS

GEOL WAYNE WALCHER FIELD BEMIS-SHUTTS

E 2176 KB c10/29/75 ^{CARD}ISSUED 12/31/75 IP P 9 BOPD + 1 BWPD
 ARB 3724-30

API 15-051-21,112

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
HEEB	3388	-1212	
TOR	3408	-1232	
LKC	3433	-1257	
BKC	3677	-1501	
CONG	3684	-1508	
SIMP	3703	-1527	
ARB	3722	-1546	
RTD	3730	-1554	

8 5/8" 253/150SX, 5 1/2" 3724
 NO LOG
 DST (1) 3712-3730/30-30-45-45, 210' HOCM
 N/W, SIP 913-859#, FP 52-46#, 96-
 96#
 MICT - CO TD, FU 3₂ BOPD N/W, NAT, A
 1000, REC LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS