

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21544-00-00
Spot: SENENW Sec/Twnshp/Rge: 30-18S-6W
4286 feet from S Section Line, 2970 feet from E Section Line
Lease Name: COCHRAN Well #: 1
County: RICE Total Vertical Depth: 3215 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3093		100 SX
SURF	8.625	208		130 SX

\$ 104.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 21 2006
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/06/2006 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Set CIBP @ 2960' and capped with 2 sacks of cement. Blew off casing at 1183'. Pulled to 950' and pumped 35 sacks of cement. Pulled casing to 575' and pumped 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C-031328
Log Tech #4737

Perfs:

Top	Bot	Thru	Comments
2974	2979		

Remarks:

Plugged through: CSG

INVOICED
DATE 12-15-06
INV. NO. 2007060984

District: 02

Signed Virgil Clothier
(TECHNICIAN)

ra

RECEIVED
Form CP-2/3
DEC 14 2006
KCC WICHITA