

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22730-00-02  
Spot: SWNWNE Sec/Twnshp/Rge: 10-29S-4E  
4428 feet from S Section Line, 2330 feet from E Section Line  
Lease Name: HOWARD Well #: 2  
County: BUTLER Total Vertical Depth: 1946 feet

Operator License No.: 30582  
Op Name: KISER, MICHAEL DBA MWK PETROLE  
Address: 508 STONE LAKE CT.  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1936		40 SX
SURF	8.625	215		104 SX

**\$63.25**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2006 10:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: MIKE KISER Company: MWK PETROLEUM CO. Phone: (316) 775-5496

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/08/2006 1:50 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

11/6/2006 -- MIRU. Sanded back at 1845'. Dump bailed 4 sacks of cement on top.  
11/7/2006 -- Shot 4-1/2" casing at 805'. POOH with 21 joints of 4-1/2" casing.  
11/8/2006 -- RIH with tubing at 265'. BPC mixed and pumped 65 sacks of 60/40 posmix with 4% gel to surface.  
Braden Petroleum #06-542 & #06-543

**Perfs:**

Top	Bot	Thru	Comments
1898	1903		

RECEIVED  
KCC DISTRICT #2  
DEC - 4 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

INVOICED  
DATE 12-15-06  
INV. NO. 2007060989

District: 02

Signed Duane P. Krueger  
(TECHNICIAN)

RECEIVED  
DEC 14 2006  
KCC WICHITA