

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23062-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 3-29S-4E  
1576 feet from S Section Line, 1062 feet from E Section Line  
Lease Name: HOWARD Well #: 5  
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 30582  
Op Name: KISER, MICHAEL DBA MWK PETROLE  
Address: 508 STONE LAKE CT.  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	787		40 SX
SURF	8.625	202		72 SX

\$ 69.88

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2006 10:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: MIKE KISER Company: MWK PETROLEUM CO. Phone: (316) 775-5496

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/08/2006 4:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

11/31/2006 -- MIRU. RIH with wire line. Tagged TD at 781'. Sanded back at 700'. Dump bailed with 4 sacks of cement on top. Shot 4-1/2" casing at 526'.

11/1/2006 -- POOH with 13 jts of 4-1/2" casing (526').

11/8/2006 -- RIH with tubing at 252'. Braden Petroleum mixed and pumped 98 sacks of 60/40 posmix with 4% gel to surface.

Braden Petroleum #06-541 & #06-544

Perfs:

Top	Bot	Thru	Comments
757	758		
754	756		

RECEIVED  
KCC DISTRICT #2

DEC - 5 2006

WICHITA, KS

INVOICED

DATE 12-15-06  
INV. NO. 2007060989

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

RECEIVED Form CP-2/3  
DEC 14 2006  
KCC WICHITA

PKG