

RECEIVED
KCC DISTRICT #2
DEC - 5 2006
WICHITA, KS

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 035-21852-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 10-04-1978

Well Operator: W. D. Short Oil Co., LLC KCC License #: 33608
(Owner / Company Name) (Operator's)

Address: P.O. Box 729 City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: Cox Edith Well #: 4A Sec. 5 Twp. 34 S. R. 6 East West

- NW - SW - NE Spot Location / QQQQ County: Cowley

1890 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2040 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 125 Cemented with: 65sx Sacks

Production Casing Size: 5-1/2" Set at: 3001 Cemented with: 250sx Sacks

List (ALL) Perforations and Bridgeplug Sets: Open Hole

Elevation: 1193 (G.L. / K.B.) T.D.: 3011 PBTD: _____ Anhydrite Depth: ?
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC instructions

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Anstine

Phone: (620) 455 - 3576

Address: P.O. Box 729 - 102 S. River Rd. City / State: Oxford, Kansas

Plugging Contractor: B.P.C. Well Plugging KCC License #: 32475
(Company Name) (Contractor's)

Address: P.O. Box 282 Burden, Ks. 67019 Phone: (620) 438 - 2856

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.

Date: 11-17-2006 Authorized Operator / Agent: Walt Short
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 06 2006
KCC WICHITA

OFFICE PHONE 221-4870

GEORGE R. MCNEISH
GEOLOGICAL ENGINEER
P. O. BOX 734
528 STATE BANK BUILDING
WINFIELD, KANSAS 67156

RESIDENCE PHONE 221-3458

5 1/2 2505*
6532
2930-2945

WELL: Cox #4-A

LOCATION: NE SW NE
5-34S-6E
Cowley County Ks.

OPERATOR: W. D. Short

CONTRACTOR: White & Ellis Drlg. Co./Rig #3

DRILLING COMMENCED: March 12, 1978

DRILLING COMPLETED: March 17, 1978

PRODUCTION:

ELEVATION: 1193 KB
1188GL

DATUM: All Measurements are taken from the
rotary bushing, 5' above ground level

ROTARY TOTAL DEPTH: 3011'

RECEIVED
DEC 06 2006
KCC WICHITA

W. E. Short Oil Co.
P. O. Box 45
Oxford, Kansas 67119

Re: Cox #4-A

Gentlemen:

The following report covers facts pertinent to the drilling of your Cox #4-A well. It includes geological tops as determined from sample analysis and correlated with drilling time log information, daily drilling depths, casing record, testing data, structural data, and sample description of zones of interest. No open hole electric log was run on this well.

FORMATION TOPS (Sample)

<u>Formation</u>	<u>Depths</u>	<u>Sub-sea Datum</u>
Topeka	1016	+ 177
Amazonia	1469	- 276
Iatan	1712	- 519
Stalnaker	1767	- 574
Perry		- 752
Hoghoooter	2167	- 974
Layton	2181	- 988
Kansas City	2363	-1170
Marmaton	2601	-1408
Ft. Scott	2663	-1470
Cherokee	2740	-1547
Mississippi	2986	-1793
Chat Porosity	3002	-1809
Total Depth	3011	-1818

DAILY DRILLING DEPTH

<u>Date,</u>	<u>Depth @ 8 A.M.</u>	<u>Footage Made Previous 24 Hrs</u>
3/12/78	Move in	
13	125 Start under Surf @	0
14	610	485
15	1587	977
16	2255	668
17	2712 (3011 TD @ 11:07 p.m.)	457

RECEIVED
DEC 06 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

W.D. Short Oil Co., LLC
102 S. River Road
PO Box 729
Oxford, KS 67119

December 13, 2006

Re: COX EDITH #4-A
API 15-035-21852-00-00
NWSWNE 5-34S-6E, 3390 FSL 2040 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



Barry Metz
Deputy Director